



## Services Schedule as at 14 April 2015

	Service	Network Provider	Retail Supplier	Capacity/ Capability  (indicative)	Description	Availability	
						Stage 1	Stage 2
<b>1.0</b>	<b>Internet</b>						
1.1	Fibre Optic Cable	Ultra Fast Fibre, Chorus, Vodafone	Various	Up to 1 gbs		•	•
1.2	VDSL Copper Cable	Chorus	Various	15-70mbs down 5-10mbs up		•	
1.3	ADSL Copper Cable	Chorus	Various	5 – 15mbs down 1mbs up		•	
1.4	Mobile Broadband	Various	Various	Up to 5mbs		•	•
1.5	Wireless Internet	Various	Various	10mbs down 1mbs up		•	•
<b>2.0</b>	<b>Telephone</b>						
2.1	Copper Cable	Chorus	Various			•	
2.2	Voice over Internet/ Fibre Optic Cable	Ultra Fast Fibre, Chorus, Vodafone	Various			•	•
2.3	Cellular	Various	Various			•	•
<b>3.0</b>	<b>Power</b>	Powerco	Various	Min 3 Phase 100A	Lot connection provided.	•	•
<b>4.0</b>	<b>Gas</b>	Vector	Various	Min. 200Kpa	Reticulation in road berms. Connection size & location to be determined at time of building.	•	•
<b>5.0</b>	<b>Water</b>	Tauranga CC	N/A	Fire: Min 100kPa Gen: Min 300kPa	Reticulation in road berms. Connection size & location to be determined at time of building.	•	•
<b>6.0</b>	<b>Wastewater</b>	Tauranga CC	N/A	Specific Design Ave. PWWF 0.7 l/s/ha.	Connection located within Lots. High flows may require Council input & specific design.	•	•
<b>7.0</b>	<b>Stormwater</b>	Tauranga CC	N/A	100% site runoff	Connection located within Lots.	•	•

Footnotes: i) Information is indicative only and enquiries should be made directly to the various service providers to confirm availability.

ii) New services reticulation and connections are the responsibility of the purchaser following issue of Title.

iii) If the service providers above cannot provide connection assistance you are may contact the Tauriko Business Estate developer Element IMF at 07 5714120 for further direction.